



LAWRENCE
LIVERMORE
NATIONAL
LABORATORY

Fusion of X-Ray and Ultrasound Images for As-Built Modeling

G. A. Clark, J. A. Jackson

November 14, 2006

Signal and Imaging Sciences Workshop, Center for Advanced
Signal and Imaging Sciences
Livermore, CA, United States
November 16, 2006 through November 17, 2006

Disclaimer

This document was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor the University of California nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or the University of California. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or the University of California, and shall not be used for advertising or product endorsement purposes.



FUSION OF X-RAY AND ULTRASOUND IMAGES FOR AS-BUILT MODELING

GRACE A. CLARK

***EE/EETD, SYSTEMS AND DECISION SCIENCES
SECTION***

JESSIE A. JACKSON

EE/DSED, SIGNAL/IMAGE PROCESSING AND CONTROL GROUP

NOVEMBER 16-17, 2006

THIS WORK WAS PERFORMED UNDER THE AUSPICES OF THE U.S. DEPARTMENT OF ENERGY BY THE UNIVERSITY OF CALIFORNIA, LAWRENCE LIVERMORE NATIONAL LABORATORY UNDER CONTRACT No. W-7405-ENG-48.

Disclaimer and Auspices Statements



This document was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor the University of California nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or the University of California. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or the University of California, and shall not be used for advertising or product endorsement purposes.

This work was performed under the auspices of the U.S. Department of Energy by University of California, Lawrence Livermore National Laboratory under Contract W-7405-Eng-48.

Agenda




- **Problem Definition**
- **Controlled Experiments with a “Phantom” Part**
- **Registration and Fusion Algorithms**
- **Experimental Results**
- **Conclusions**

ME Techbase, "Process Development and Implementation of NDE-FEA Coupling for Numerical Analysis"



- Created a RD&T Roadmap for Engineering Centers (CNDC and CCE)
- Multi-modal Sensor Fusion and Flaw Recognition for **"As-Built Modeling"**
- Processed X-Ray CT and Ultrasonic images from a known "phantom"




As-Built Modeling: Fabrication Errors Can Sometimes Be Significant



As-Designed



As-Built



ENGINEERING CCE AND CNDC TECHBASE '04 PROJECT, "PROCESS DEVELOPMENT AND IMPLEMENTATION OF NDE-FEA COUPLING FOR NUMERICAL ANALYSIS," ED KOKKO, GRACE CLARK, DIANE CHINN, DAVE CHAMBERS

ENG-03-0051-0 5
Clark-11/10/06, UCRL-CONF-217090

Grace A. Clark, Ph.D.





The Literature Contains No Fusion of X-Ray and Ultrasound NDE Imagery



- The medical literature contains some fusion results, but they are not generally useful for NDE:
 - Allowable power levels are much lower for medicine
 - Attenuation effects are much different in medicine
 - Qualitative results (visual inspection) are usually sufficient
 - Fiducial marking is routine in medicine, but often not possible in NDE at LLNL
- Image registration is the “long pole in the tent” for fusing X-ray and Ultrasound NDE Images - Attempts have been unsuccessful
 - There are separate scanning systems for X-ray and Ultrasound, so mechanical registration is impossible
 - Image reconstruction and registration are coupled
 - Scaling the UT image requires ray tracing, event picking, and velocity estimation (as in seismic processing)
 - Difficult to automate

Our Test Part Consists of 3 Concentric Cylinders Made of **Aluminum**, **Cellulose** and **Epoxy**



ENG-03-0051-0 7
Clark-11/10/06, UCRL-CONF-217090

Grace A. Clark, Ph.D.



CT and UT Measure Different Material Properties. Each Modality Has **Strengths** and **Weaknesses**.

Grace Clark



CT (X-Rays)

Measures X-Ray Attenuation

$$A = f[E_A, \rho, Z]$$

where :

E_A = Energy Applied

ρ = Density

Z = Atomic Number (# protons)

Strengths:

- A strong function of Z ($\sim Z^r$)
- High spatial resolution (good for observing part geometry)
- Spatial scaling is automatic

Weaknesses:

- *Not very sensitive to changes in density - Not good for detecting closed cracks*

UT (Ultrasonics)

Measures reflected acoustic energy

$$R = g[\rho, E]$$

where :

ρ = Density

E = Modulus of Elasticity

= Young's Modulus


Strengths:

- *Good for detecting small changes in density and modulus*
- *Good for detecting closed cracks*

Weaknesses:

- *Low spatial resolution due to temporal “ringing” of band-limited ultrasonic transducers*
- *Spatial scaling is complex, difficult*

Two Image “Slices” Demonstrate the Strengths and Weaknesses of CT and UT



The Epoxy-Cellulose Interface Has **Low Contrast With CT**, but **Much Higher Contrast With UT**



The Epoxy - Cellulose Interface:

- Epoxy and Cellulose have approximately the same density and modulus:

Composition

► Density:

$$\rho_{Epoxy} \approx \rho_{Cellulose}$$

► Coefficient of Elasticity:
(Young's Modulus)

$$E_{Epoxy} \approx E_{Cellulose}$$

► Atomic Number:


$$Z^{eff}_{Epoxy} \approx Z^{eff}_{Cellulose}$$




- UT can detect interfaces well
- CT is minimally effective for interface detection, good for geometry characterization

- The other interface contrasts are strong for both CT and UT

X-Ray Images (Radiographs) are Acquired by Fixing the X-Ray Source and Rotating the Object



Ultrasound Images are Acquired Using a Separate Scanning System: Source is Fixed, Object is Rotated




ENG-03-0051-0 12
Clark-11/10/06, UCRL-CONF-217090


Grace A. Clark, Ph.D.



***Ultrasound Images are Acquired in Pulse-Echo Mode,
Scanning the Transducer Vertically as the Part is Rotated***




Raw A-scan (Time Waveform)




*An Ensemble of Ultrasonic A-Scans Forms a **B-Scan***




B-Scan Plotted as an Ensemble of Time Waveforms



B-Scan Plotted Using Pixel Intensity




*An Ensemble of B-Scans forms a **3D Volume***



Summary of Horizontal Slice 40: Epoxy and Aluminum

Both CT and UT Show the Epoxy-Al Interface





Summary of Horizontal Slice 20: Epoxy, Cellulose, Air

Cellulose-Epoxy Interface is Visible Only in the UT Image




Sketch





Cellulose-Epoxy
Interface is **NOT**
Delineated


CT



UT




Cellulose-Epoxy
Interface is **Clear**




Optimal (Desired) Approach to Fusion: Fully Automatic Processing at All Steps

Grace Clark




Suboptimal Semi-Manual Fusion: Build a “UT Edge Map” and Superimpose it on the CT Image




The *System Model* and *Super-Resolution Algorithms* Are Summarized in Block Diagrams





System Model



Super-Resolution Algorithms




Super-Resolution Result: Resolution is Enhanced in the Ultrasound Polar Plots of *Slice 20*



An “*Ultrasound Edge Map*” Polar Plot is Created from *Slice 20* Using the Super-Resolution Results



By Manually Comparing the CT Image and the UT Edge Map,
A Spatially Scaled UT Edge Map can be Determined:
(*Ray Tracing, Event Picking and Velocity Estimation are Done Manually*)




Fusion: The “*UT Edge Map*” is Superimposed on the CT Image of *Slice 20* to Show the Cellulose-Epoxy Interface




Slice 20

X-Ray CT Image:

*Cellulose-Epoxy Interface
is Not Visible*



X-Ray CT Image
with the “*UT Edge Map*”
Superimposed:
Cellulose-Epoxy Interface



Conclusions



- **We demonstrated a semi-manual method for fusing X-ray and Ultrasound images**
 - **Using super-resolution algorithms to build an “edge map”**
 - **Manually performing ray tracing, even picking, and velocity estimation**
- **Future work:**
 - **Automating the registration and fusion processes**